

# Bombala Treated Water supply Presentation

# Bombala Water Quality

## 1. Water quality is variable depending on drought or floods

1. Stagnant water with sludge build up in droughts
2. High turbidity and contamination washed into river during high rain events

## 2. Intermittent discoloured water into network

1. Settled turbidity in water network – when suspended (dirty water complaints)

## 3. Iron & manganese:

1. Water containing iron and manganese can stain clothes, discolour plumbing fixtures, and sometimes add a “rusty” taste and look to the water.
2. These materials form a coating on the inside of the water main and, when they break loose, a customer will sometimes complain of “dirty” water.
3. can look like crystal clear water leaving plant but turn red/brown colour in network

## 4. Bore drilling & feasibility tests

1. Note that bores were only ever a supplement to river supply
2. Drilling and feasibility/sustainability testing of bore holes
  1. No sustainability of supply
  2. Poor volume L/s

# Issues with Upgrade of the Current Bombala WTP

- Many assets are 39 years old which is excessive for Mech/Elec systems and equipment not maintained properly for many years until 2017.
- Incorrect clarification to remove solids
- Incorrect iron & manganese oxidation process
- No control of taste/odour and Trihalomethanes (THS)
- Requires extensive upgrades to chemicals area needed for reliability, WHS and regulatory compliance
- Some structural uncertainty that it will in fact last the distance (eg filter movement)
- Clarifiers may not be reliable treatment process for high colour/low turbidity/changing alkalinity and water temperature conditions
- Risk of plant offline for longer than expected (leading to increased CAPEX)
- Estimated carting of water supply ~ \$14,000/d
- Uncertain residual life of filters and clarifiers
- Continued confined space at filter valves (WH&S)

# New WTP: Site Layout



- 1) New wash water pipe to thickener
- 2) Wash water and sludge pipe from new plant to wash water tank
- 3) New sludge line to lagoons
- 4) Supernatant return to plant inlet
- 5) Wash water flowmeter
- 6) Supernatant flowmeter

- A) Mixed wash water tank - 6 m diameter (50 m3) and pump station
- B) Thickener
- C) Supernatant Return Tank and PS
- D) CIP waste tank
- E) Chlorine Building
- F) Fluoride Building
- G) Mixed Oxidation Tank
- H) UV

Option 2 & 3 – New WTP location

# Projected Timeline



- **Contract/Project Management appointment –**
  - out end January 2021 & appointed 1<sup>st</sup> Week in March
- **Design & Construct contract – Development and tender –**
  - awarded early May 2021
- **Site establishment/Mobilisation –**
  - On Site end May 2021
- **Construction Period – 18 months –**
  - Commissioning end November 2022
- **Contractor O&M proving period (Quality of water – plant performance)**
  - 3 months after commissioning

# Recommended Option

Item	Upgrade existing WTP Clarifier/filters+ GAC+ Disinfection/UV + THM stripping	Preferred Option New - WTP DAF/MF + GAC + Disinfection/UV + THM stripping
Performance- Water Quality	√√ (clarifier uncertain )	√√√
Operability	√√	√√√√
Env&WHS	√√ ( ongoing poor access to filter valves)	√√√
Construction complexity	√ ( existing structure and uncertain time offline needing carting in water risks)	√√√√
Easy procurement	√√√√	√√√√



# Recommendations

- The key features of the preferred Option to go to the next stage of this project are;
  - Treatment process; Pre-oxidation + Dissolved Air Flootation (DAF) + Membrane filtration + GAC + UV+ chlorination then chloramination + THM stripping
  - Buildings: designed to suit bushfire rating of the area (as well as some structures e.g.mens shed is not on Council land so will be left undisturbed)
  - Location; at existing old house site and decommission existing WTP but possibly reuse existing building for some of the chemical systems and for administration/spares storage
  - New wash water/sludge system; wash water/sludge holding tank and pumps to thicken and then concentrated sludge to existing sludge ponds and supernatant tank and supernatant return pumps to WTP inlet
- Construct separate purpose built building for chlorination
- Engage specialist contractor for purpose built fluoridation building
- It is also not recommended to pursue any further the option of groundwater (Bores) (based on test results in March 2020)

# Thank you

